

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work: Improvements to Drain at Somanna Garden Main Road from 1st cross saptagiri layout to SWD in Ward No. 09 In vidyaryanapura sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	498.84	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	115.56	Rupees One Hundred Fifteen and Fifty Six Paise Only
2	67.26	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
3	30.24	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4905.36	Rupees Four Thousand Nine Hundred Five and Thirty Six Paise Only
4	5.32	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5490.72	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only
5	1018.19	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	306.72	Rupees Three Hundred Six and Seventy Two Paise Only


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	165.26	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal , coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	6198.12	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only
7	11.57	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	69805.80	Rupees Sixty Nine Thousand Eight Hundred Five and Eighty Paise Only
8	473.90	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.34	Rupees One Hundred Six and Thirty Four Paise Only


 Executive Engineer
 Byatarayanapura Division
 BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಬೆಂಚರ್ ಪಡೆದಿಲ್ಲವನ್ನು
 ಶಿದ್ಧಪಡಿಸಿ ಸಂಖ್ಯೆ.....(Nil)
 ಶಿದ್ಧಪಡಿ ಮಾದಿ/ಇಲ್ಲದೆ
 ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ


 01.01.16